

SOR
for

Name of Work: Misc Electrical power wiring and network wiring works for newly placed 39 nos of modular furniture for research scholar lab at CSE dept at IITG campus

Sl. No.	Description of Item	Unit	Qty.	Rate in Fig (in Rs.)	Rate in Words (in Rs.)	Amount (Rs.)
1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	b).2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	585			
2	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 20 mm	Mtr	180			
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.					
	b). 15/16 A switch	Each	39			
	c). 3 pin 5/6 A socket outlet	Each	117			
4	Supplying and drawing of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed Steel/ PVC conduit as required.					
	a). 1 run of cable	Mtr	585			
5	Providing, fitting & fixing of modular RJ-45 point (of approved brand) with compatible GI box, cover plate etc.	Each	39			
TOTAL AMOUNT						-

NB: Rates quoted are inclusive of GST

Seal and Signed of contractor